

MAPLE LANE ESTATE - STAGE 02

MAPLELANE PROJECTS PTY LTD

CITY OF BALLARAT

CONSTRUCTION NOTES (CITY OF BALLARAT)

SITE MANAGEMENT

Prior to commencement of works on site, the contractor must ensure that all matters relating to the Occupational Health and Safety Act 2004, including all relevant regulations, have been addressed. In particular, the required notifications must be conveyed to the Victorian Workcover Authority - Health & Safety division with respect to trenching operations. Details of the contractors occupational health & safety procedures must be lodged with the Superintendent prior to commencement of works.

1. All native trees and shrubs to be retained unless road construction necessitates their removal or removal is directed by the engineer. A town planning permit is required for the removal of native trees and/or vegetation. The removal or retention of any existing trees must be in accordance with the approved landscape plan, or else approval will be required from the City of Ballarat landscape approvals officer.

2. Prior to commencement of works, the contractor must submit a Construction Management Plan (CMP) to the Superintendent for approval. The contractor must comply with the recommendations of the Environment Protection Authority publication No.275 "Construction techniques for sediment pollution control". Appropriate siltation control is to be maintained throughout the construction and maintenance period of the works.

GENERAL

3. All levels are in metres to Australian Height datum and taken from Level Plan by Beveridge Williams & Co. Pty Ltd.

4. All works to be carried out in accordance with AS2124-1992 General Conditions of Contract, City of Ballarat and Infrastructure Design Manual (IDM) current specification and standard drawings and to the satisfaction of the Superintendent and City of Ballarat works supervisor. The contractor shall ensure that they are conversant with all current revisions, amendments and updates that have been made to these standards.

5. The Superintendent, Council and all service authorities should be notified by the contractor, in writing, seven days prior to commencement of the works.

6. All existing services shall be confirmed to have been located prior to commencement of works. Where services have not been previously proven or located the Contractor shall make allowance or be satisfied that construction in accordance with the design can be achieved.

7. Where works are in the vicinity of existing services these services are to be located and the various authorities notified prior to the commencement of works.

8. The contractor shall erect and maintain all shoring, planking and strutting, dewatering devices, barricades, signs, lights, etc., necessary to keep works in a safe and stable condition and for the protection of the public.

9. Before commencement of works on trenches in excess of 1.5m deep, the civil contractors construction supervisor must give notice in writing of such proposals to Worksafe Victoria in accordance with Part 5.1, Division 4 of the Occupational Health & Safety regulations (2007) and undertake safety precautions in trenching operations in accordance with Workcover's Code of Practice (1988).

10. Lots to be graded & left clean to the satisfaction of the engineer. Finished levels to be compatible with lots adjoining this stage.

11. On completion the contractor is responsible for the removal of all rubbish and spoil from site. No surplus trees, vegetation or other material is to be burnt on site.

12. Reserves to be free draining and to be left in a condition satisfactory to the Superintendent and City of Ballarat works supervisor.

13. All TBM's and control points are to be maintained and protected at all times during construction. Should any marks be disturbed, the contractor will immediately notify the consultant to arrange re-statement at the contractors expense.

EARTHWORKS

14. All areas shown on the drawings to be cut or filled are to be stripped of topsoil and all topsoil must be stockpiled on site.

15. Upon completion of the bulk earthworks topsoil is to be spread to a depth of 100mm over the nominated area and graded to finished levels shown on the drawings.

16. Batters to be 1 in 5 for fill and 1 in 5 for cut unless noted otherwise.

17. All nature strips and batters shall be covered with 100mm min. depth topsoil and seeded with an approved seed and fertilizer mixture.

18. Filling in all properties and road reserves is to be carried out using approved clay fill. Top soil and all vegetable matter to be stripped from site prior to filling. All filling to be carried out in 150mm layers and compacted to 95% of max dry density. All filling to comply with AS3798-2007, Section 8.2, Level 1 "Guidelines on Earthworks for Commercial and Residential Developments". A fill report must be submitted showing compliance from a NATA registered soil testing laboratory.

19. Importing Fill:- All imported fill must be tested by a NATA approved laboratory to ensure it is suitable for use on site, and any contaminants are within accepted levels. Under No circumstances should fill material enter or leave the site without the permission of the Superintendent or prior to it being appropriately tested.

20. All fill material shall be clean, uniform and free of organic matter and meet requirements of AS 3798-2007 "Guidelines on Earthworks for Commercial and Residential Developments".

21. Fill material should be placed in layers of uniform thickness, deposited systematically across the fill area. The contractor must excavate or "box" into the existing surface at the edge of fill to provide a suitable junction with the existing surface and to avoid feathered edges.

22. Prior to disposal of excess spoil the truck route and disposal location is to be approved by the Superintendent prior to commencing to dispose of spoil.

23. All vehicles transporting fill material to and from the site must have appropriate measures in place to ensure that material does not get onto roads and into stormwater systems and natural waterways.

24. Cut batters behind vehicular accesses must not exceed maximum grade of 1 in 5.

25. Before any loose layer of fill is compacted, the material and its moisture condition should be as uniform as is practicable throughout its depth.

26. If there is a delay in the placement of subsequent fill layers, previously accepted layers should conform with the specification before further fill is placed. If these layers have wetted up or dried out, they may inhibit compaction or cause heaving of subsequent layers. In these instances, drying or wetting of the fill by the contractor will be required to achieve optimum compaction.

27. All lots are to be brought to a finished surface level and top soiled to ensure that front boundaries are a minimum of 150mm above the top of kerb.

28. The maximum particle size of any rocks or other lumps within the fill layer, after compaction, should not exceed 100mm or two-thirds of the compacted layer thickness.

29. Fill is to be tested in increments of depth not greater than 500mm.

30. Fill batter faces are to be overfilled and cut back. The trimmed and compacted face should have a roughened surface to reduce runoff.

31. The surface of all fill layers must be shaped to provide drainage and to prevent ponding.

32. All fill to be compacted to that shown or 95% standard density or better. Moisture content must be in the range of -10% to +5% optimum.

33. Where fill placement is less than 200mm stripping of topsoil may be deleted, in which case the contractor shall remove all organic matter from existing surface prior to placing topsoil.

34. Filling to be completed prior to sewer and drainage construction, unless approved by the Superintendent and relevant Authority.

ROADWORKS

35. 100mm dia. agricultural pipe drains (Refer BCC SD-D2-1) to be placed behind kerb and channel or as directed by Superintendent and at minimum grade of 1 in 250.

36. The water conduit offset from the lot boundary is given on the water reticulation plan. The contractor must construct conduits to accord with the given offset and ensure that the concreter marks the kerb and footpath exactly above the conduit.

37. All footpaths and shared pedestrian/bicycle paths are to be 125mm thick concrete as per IDM Standard Drawings SD205, 210, 215, 220 and 225.

38. Telecommunication contractor to be notified seven (7) days prior to concrete works being placed.

39. Electrical distribution pits within footpaths are to be a minimum of 300mm within the edge of the path. Concrete is to be placed around distribution pits to a minimum depth of 200mm.

40. Existing road works to be reconstructed as required to provide, without discontinuity, a connection in accordance with design levels and grades.

PAVEMENT

41. Pavement shall be constructed in accordance with construction plans, IDM and City of Ballarat Specifications and Standard Drawings.

42. Modification of the pavement requires approval by the City of Ballarat.

43. Prior to the commencement of the works, the contractor shall provide to Superintendent and Council the following information:-

- Source of quarry material.
- Optimum Moisture Content and Maximum Modified Dry Density of the F.C.R. to be used (from NATA approved laboratory).
- If the source of the quarry material is changed during the course of the works, new test results shall be provided.

51. Subgrade, sub base and base compaction densities shall be in accordance with that shown in Table 1 and Clause 304.07 of Vicroads Standard Specification for Roadworks and Bridge works.

52. Compaction testing must be undertaken by NATA approved laboratory.

53. Compaction testing and proof rolling shall be undertaken on same day.

54. Superintendent and Council must be given minimum 24 hours notice of proof roll.

55. All pavement areas shall be proof rolled in the presence of Superintendent and Council Inspection Engineer, at the expense of contractor and in accordance with AS 3798 and Clause 173 and 204.12 of Vicroads Standard Specification for Roadworks and Bridge works.

56. If more than 20 percent of pavement area fails proof roll then total area must be reworked.

57. The next layer of pavement shall not be placed until previous layer has been approved. Following approval the contractor shall ensure that the next layer is placed within a reasonable period of time. If this is not possible it is the contractors responsibility to protect the pavement already approved. Failure to do so shall render contractor responsible for any pavement damage and rectification.

58. All geotechnical and compaction results are to be submitted to Superintendent and Council.

DRAINAGE

59. Drainage and pits to be set out from offsets shown rather than from centreline pipe chainages.

60. Stormwater pits shall be reinforced concrete and constructed in accordance with IDM and City of Ballarat Specifications and Standard Drawings. Minimum drop through pit shall be 20mm unless shown otherwise. For specific details refer Pit Schedule and IDM Standard Drawings SD 400 to SD 495. Minimum Concrete Strength Fc 25MPa at 28 Days.

61. Precast pits are permitted where manufacturer can demonstrate compliance with requirements of IDM and City of Ballarat Specifications and Standard Drawings.

62. Pit Covers and surrounds in trafficable areas shall be Class D Gatic or similar all other area shall be Class B precast reinforced concrete unless otherwise shown.

63. All pipes under pavement to be RCP(RR) Class 3. All 150mm diameter pipes to be UPVC SN4. Pipes other than under pavement or trafficable area may be approved ribbed stormwater pipe such as Blackmax or Stormpro®. Where ribbed stormwater pipe is used embedment shall be to manufacturers specification.

64. Pipe trenches beneath the road pavement and footpath to be backfilled with 20mm Class 3 F.C.R. At all other locations backfill with an approved material to a minimum 300mm above top of pipe. Backfill material shall be in maximum 150mm layers and in accordance with BCC Standard Drawing SD-D8-1.

65. Pipe trenches behind kerb and in easements or nature strips to be backfilled with Red Dredge in 150mm layers to 300mm above top of pipe and in accordance with BCC Standard Drawing SD-D8-1.

66. Easement Property Inlets at rear of property shall be 100mm PVC SN4 constructed in accordance with BCC Standard Drawing SD-D9 located 1.0m. from the low corner of the lot unless otherwise shown.

67. House Drain Property Inlets at front of property shall be 100mm PVC SN4 constructed in accordance with BCC Standard Drawing SD-D9 and located 5.0m from the low corner of the lot unless otherwise shown. Lots denoted H shall be connected to kerb. Lots denoted PI shall be connected to pipe to pit.

68. Property Inlets for allotments shall be at a sufficient depth to control drainage at minimum of 1 in 200 fall from all points within the building area.

69. All proposed drainage stubs to be blanked off at end of pipe with timber planks to the satisfaction of the Superintendent and Council supervising engineer.

70. All drainage backfill under pavement shall be tested and results provided to the Superintendent.

SERVICES

71. All service trenches under footpath, vehicular crossings and kerb & channel shall be backfilled with 20mm Class 2 crushed rock. All service conduit trenches under road pavement shall be backfilled with compacted 2% cement treated crushed rock.

72. Gas and water conduits and mains must be laid in trenches excavated and backfilled by the contractor. Conduits are to be 50mm diameter Class 12 PVC service conduits laid at a minimum depth of 600mm below finished surface level. Contractor shall supply all sand embedment. The contractor shall give the gas contractor 7 days notice prior to commencing work.

73. Telecommunications conduits and cable ducts must be laid in trenches excavated and backfilled by the contractor. Conduits are to be type and size as shown on approved telecommunications plans and laid at a minimum depth of 600mm below finished surface level. Contractor shall supply all sand embedment. The contractor shall give the Telecommunications contractor 7 days notice prior to commencing work.

74. Electrical conduits and cables must be laid in trenches excavated and backfilled by a VEDN approved contractor. Conduits are to be type and size as shown on approved electrical plans and laid at a minimum depth of 600mm below finished surface level. Contractor shall supply all sand embedment. The contractor shall give the Electrical contractor 7 days notice prior to commencing work.

75. All conduit ends immediately upon placement of the conduit must be plugged.

76. Conduits under footpaths to be 450mm deep extending a minimum of 250mm either side of the path. The footpath above the conduits is to be marked with two contraction joints over the conduits 400mm apart.

77. The reinstatement and compaction of public authority service trenches shall be the contractor's responsibility.

78. The contractor must note the existence of telecom, gas, power, water and any other services in the area prior to tendering. Any disturbance to existing services, footpaths etc. shall be rectified at the contractor's expense to the satisfaction of the superintendent and relevant service authority as appropriate.

ATTENTION TO CONTRACTOR

In accordance with Clause 15 of AS2124 Australian Standard Conditions of Contract, the contractor must ensure the safety of the contractor's employees and all other people who are on or adjacent to the site. The contractor must comply with the Victorian Occupational Health and Safety Act

79. The contractor must ensure that all people employed on the site wear approved safety apparel. This includes safety helmets, vests, safety boots, eye & ear protection, where appropriate.

80. The contractor shall reinstate any affected footpath, vehicle crossing and nature strip to the satisfaction of the City of Ballarat

81. Beveridge Williams & Co Pty Ltd is responsible for design of the works. Any proposed alterations to the design shall be directed to the consultant for approval prior to making any alterations to the design.

82. The contractor is directly responsible for the setout. Should actual site conditions conflict in any way with that documented, the contractor must contact the office of Beveridge Williams & Co. Pty. Ltd. for clarification before proceeding.



SITE PLAN

NOT TO SCALE

DRAWING INDEX

DRAWING No.	TITLE	REV
1801844-02-001	COVER SHEET	B
1801844-02-002	TYPICAL ROAD CROSS SECTIONS & GENERAL DETAILS	A
1801844-02-010	LAYOUT PLAN	B
1801844-02-100	ROAD LONGITUDINAL SECTIONS	A
1801844-02-200	ROAD CROSS SECTIONS HATHAWAY CLOSE SHEET 1 OF 3	A
1801844-02-201	ROAD CROSS SECTIONS HATHAWAY / SERVICE ROAD SHEET 2 OF 3	A
1801844-02-202	ROAD CROSS SECTIONS SERVICE ROAD / DRIVEWAY SHEET 3 OF 3	A
1801844-02-300	COURTBOWL LAYOUT & INTERSECTION DETAILS (SHEET 1 OF 2) HATHAWAY CLOSE AND SERVICE ROAD	A
1801844-02-301	INTERSECTION DETAILS (SHEET 2 OF 2)	A
1801844-02-350	SINGAGE AND LINEMARKING	A
1801844-02-400	DRAINAGE LONGITUDINAL SECTIONS (SHEET 1 OF 2)	A
1801844-02-401	DRAINAGE LONGITUDINAL SECTIONS & PIT SCHEDULE (SHEET 2 OF 2)	A

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
P1	DRAWING INDEX UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					



Designed Date P.HUNJAN 17.10.2020
Drawn P.HUNJAN
Approved Date J.SPARK 17.10.2020
PS Number PS837926A



Beveridge Williams


Suite 3/180 Eleanor Dr
Lucas VIC 3350
ph: 03 5327 2000
www.beveridgewilliams.com.au





Project Details MAPLE LANE ESTATE
STAGE 02
CITY OF BALLARAT
Drawing Title COVER SHEET

Sheet 01 of 12






Scale NOT TO SCALE

Project Ref 1801844 Stage No 02 Drawing No 001 Rev B





- CONCRETE JOINTING NOTES**
1. SAW JOINTS ARE TO BE PLACED AT A MAXIMUM 5m SPACING AT INTERSECTIONS AND CONSTRUCTED 18-24 HOURS AFTER POURING.
 2. TRANSVERSE/CONTRACTION JOINTS ARE TO BE PLACED AT A MAXIMUM SPACING OF 15m.
 3. ALL JOINTS SHALL BE LOCATED AND SPACED IN ACCORDANCE WITH 'CEMENT AND CONCRETE ASSOCIATION OF AUSTRALIA - CONCRETE PAVEMENT DESIGN FOR RESIDENTIAL STREETS 1997'



ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
P3	DRIVEWAY TYPICAL SECTION UPDATED	03.06.21	P.H.	R.C.					
P2	PAVEMENT PROFILE AND KERB UPDATED	23.03.21	P.H.	M.J.					
P1	SERVICE ROAD CROSS SECTION UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					




Designed Date: P.HUNJAN 17.01.2020
 Drawn: P.HUNJAN
 Approved Date: J.SPARK 17.01.2020
 PS Number: PS837926A



Project Details: MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT
 Drawing Title: TYPICAL ROAD CROSS SECTIONS & GENERAL DETAILS

Sheet 02 of 12	
Scale: AS SHOWN	
Project Ref: 1801844	Stage No: 02
Drawing No: 002	Rev: A



FILL NOTES

- FILL MATERIAL SHOULD BE PLACED IN LAYERS OF UNIFORM THICKNESS, DEPOSITED SYSTEMATICALLY ACROSS THE FILL AREA. THE CONTRACTOR MUST EXCAVATE OR "BOX" INTO THE EXISTING SURFACE AT THE EDGE OF FILLS TO PROVIDE A SUITABLE JUNCTION WITH THE EXISTING SURFACE AND TO AVOID FEATHERED EDGES.
- THE METHOD OF EXCAVATION, TRANSPORT AND DEPOSITING OF FILL MATERIAL SHOULD ENSURE THAT FILL IS PLACED IN A MIXTURE AS UNIFORM AS IS PRACTICABLE. EACH FILL LAYER THICKNESS SHALL BE LESS THAN 300mm, LOOSE THEN COMPACTED TO THE SPECIFIED RELATIVE COMPACTION AND TESTED BY THE SPECIFIED TEST METHODS.
- BEFORE ANY LOOSE LAYER OF FILL IS COMPACTED, THE MATERIAL AND ITS MOISTURE CONDITION SHOULD BE AS UNIFORM AS IS PRACTICABLE THROUGHOUT ITS DEPTH.
- THE MAXIMUM PARTICLE SIZE OF ANY ROCKS OR OTHER LUMPS WITHIN THE FILL LAYER, AFTER COMPACTION, SHOULD NOT EXCEED TWO-THIRDS OF THE COMPACTED LAYER THICKNESS.
- IF THERE IS A DELAY IN THE PLACEMENT OF SUBSEQUENT FILL LAYERS, PREVIOUSLY ACCEPTED LAYERS SHOULD CONFORM WITH THE SPECIFICATION BEFORE FURTHER FILL IS PLACED. IF THESE LAYERS HAVE WETTED UP OR DRIED OUT, THEY MAY INHIBIT COMPACTION OR CAUSE HEAVING OF SUBSEQUENT LAYERS. IN THESE INSTANCES, DRYING OR WETTING OF THE FILL BY THE CONTRACTOR WILL BE REQUIRED TO ACHIEVE OPTIMUM COMPACTION.
- FILL IS TO BE TESTED IN INCREMENTS OF DEPTH NOT GREATER THAN 500mm.
- FILL BATTER FACES ARE TO BE OVERFILLED AND CUT BACK- THE TRIMMED AND COMPACTED FACE SHOULD HAVE A ROUGHENED SURFACE TO REDUCE RUNOFF.
- THE SURFACE OF ALL FILL LAYERS MUST BE SHAPED TO PROVIDE DRAINAGE AND TO PREVENT PONDING.
- ALL FILL TO BE COMPACTED TO 95% STANDARD DENSITY OR BETTER. MOISTURE CONTENT MUST BE IN THE RANGE OF -10% TO +5% OPTIMUM.
- THE CONTRACTOR IS RESPONSIBLE FOR TESTING OF THE FILL AT LEVEL 1 STANDARD. AT THE COMPLETION OF THE WORKS THE CONTRACTOR SHALL SUPPLY THE SUPERVISING ENGINEER WITH A CERTIFICATE FROM A NATA APPROVED GEOTECHNICAL ENGINEER CERTIFYING THAT FILL MEETS ABOVE REQUIREMENTS.
- FILLING TO BE COMPLETED PRIOR TO SEWER AND DRAINAGE CONSTRUCTION.

LEGEND - LAYOUT PLAN

- STORMWATER DRAIN, PIT & PROPERTY INLET
- MELBOURNE WATER DRAIN & PIT
- SWALE DRAIN
- SEWER & MAINTENANCE STRUCTURES
- HOUSE DRAIN
- SERVICE CONDUITS
- TACTILE PAVERS (INDICATIVE ONLY)
- ELECTRICITY (UNDERGROUND)
- ELECTRICITY (OVERHEAD)
- OPTIC FIBRE
- TELECOMMUNICATIONS
- GAS
- WATER
- RECYCLED WATER
- EXISTING ELECTRICITY (UNDERGROUND)
- EXISTING ELECTRICITY (OVERHEAD)
- EXISTING GAS
- EXISTING OPTIC FIBRE
- EXISTING TELECOMMUNICATIONS
- EXISTING WATER
- EXISTING RECYCLED WATER
- EXISTING STORMWATER DRAIN
- EXISTING SEWER
- EXISTING HOUSE DRAIN
- EXISTING SWALE DRAIN
- EXISTING SURFACE LEVEL
- FINISHED BUILDING LINE LEVEL
- TOP OF RETAINING WALL
- FINISHED RIDGE LINE LEVEL
- TOP OF RETAINING WALL
- BOTTOM OF RETAINING WALL
- RIDGE LINE
- RETAINING WALL
- ZERO LOT LINES
- PAVEMENT TREATMENT
- STRUCTURAL FILL > 300mm DEEP
- DIRECTION OF FALL
- OVERLAND FLOW
- ALLOTMENT TO BE GRADED EVENLY IN DIRECTION OF FALL TO LEVELS INDICATED
- CONCRETE EDGE STRIP WITH SUBSOIL DRAIN
- "NO ROAD" SIGN & BARRIER
- LIMIT OF WORKS
- EXISTING TREE TO BE REMOVED
- PERMANENT SURVEY MARK
- TEMPORARY BENCH MARK
- PROPOSED DRIVEWAY
- TREE PROTECTION ZONE (TPZ)

SERVICE OFFSET TABLE

Location	Gas		Water		Electricity		Telecommunication		Sewer	
	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)	Side	Offset (m)
HATHAWAY CLOSE	E	2.10	E	2.80	W	2.90	W	2.20	E	1.00
SERVICE ROAD	S	11.42	S	12.10	N	2.80	N	2.10	N-Ex	1.00
COURT BOWL HEAD		2.10		2.55		3.15		2.95		

NOTE: STREET TREES ARE TO BE PLANTED IN THE CENTRE OF ALL NATURE STRIPS

ROAD LAYOUT TABLE

Road Name	Reserve Width (m)	Road Width (m)			Kerb Type		Verge Width (m)	
		Lip to Lip	Inv to Inv	Back to Back	Nth/West	Sth/East	Nth/West	Sth/East
HATHAWAY CLOSE	18.00	6.70	7.60	7.9	600 B2	600 B2	3.50	3.50
SERVICE ROAD	10.15	4.60	5.50	5.80	600 B3	600 B2	2.75	-

NOTES

- ALL SERVICES SHOWN ARE PRELIMINARY AND SUBJECT TO AUTHORITY ADVICE & DETAILED DESIGN.
- EXISTING SERVICES SHOWN ARE INDICATIVE ONLY AND TO BE VERIFIED PRIOR TO DETAILED DESIGN AND CONSTRUCTION.
- ALL EXISTING DRAINAGE PITS AND SEWER MH WITHIN NEW WORKS TO BE ADJUSTED TO NEATLY MATCH NEW FINISH SURFACE.
- ALL EXISTING OPEN DRAINS WITHIN NEW WORKS TO BE CLEANED, DE-SLUDGED AND BACKFILLED TO LEVEL 1 SUPERVISION.
- THE PLAN OF SUBDIVISION IS SUBJECT TO APPROVAL FROM THE RELEVANT AUTHORITIES. LOT BOUNDARIES, EASEMENTS, RESERVES AND RESTRICTIONS MAY BE AMENDED OR ADDED TO THIS PLAN.
- CONTRACTOR TO ENSURE REMOVAL OF SEPTIC TANK PRIOR TO CONSTRUCTION COMMENCEMENT.

WARNING
BEWARE OF UNDERGROUND SERVICES
 The locations of underground services are approximate only and their exact position should be proven on site. No guarantee is given that all existing services are shown. Locate all underground services before commencement of works.
DIAL 1100 BEFORE YOU DIG
 www.1100.com.au

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN	APP	REV	DESCRIPTION	DATE	DRN	APP
P4	PLANS UPDATED AS PER COUNCIL COMMENTS	19.05.21	P.H.	M.J.					
P3	PROPOSED EASEMENT SHOWN	09.02.21	P.H.	R.C.					
P2	PROPOSED GAS UNDER DYSON DRIVE NOTE ADDED	15.12.20	P.H.	R.C.	B	HOUSE DRAINAGE CONNECTIONS AMENDED	22.07.21	L.R.	R.C.
P1	SERVICE ROAD AND LOT LEVELS UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.	P5	LAYOUT UPDATED AS PER COUNCIL COMMENTS	03.06.21	P.H.	R.C.

Maple Lane Estate

Scale: 0 5 10 20 30 40 50

Designed Date: P.HUNJAN 17.10.2020
 Drawn: P.HUNJAN
 Approved Date: J.SPARK 17.10.2020
 PS Number: PS837926A


BW Beveridge Williams
 Suite 3/180 Eleanor Dr
 Lucas VIC 3350
 ph: 03 5327 2000
 www.beveridgewilliams.com.au

Project Details: MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT
 Drawing Title: LAYOUT PLAN


Sheet 03 of 12
 Scale: 1:500 @ A1
 Project Ref: 1801844 Stage No: 02 Drawing No: 010 Rev: B

\\bawfile1\p1\Drawings\1801844 - 255 Dyson Drive, Alfreton, Eng\Stage 2\Drawings\1801844-02-010-LAY.dwg

---	EXISTING SURFACE
—	DESIGN SURFACE




CH RTP 22.257




CH LTP 17.723


SERVICE ROAD CROSS SECTIONS




CH TP 97.287




CH 85.193
HATHAWAY CLOSE CROSS SECTIONS




CH 65.157



CH TP 41.559



CH TP 39.596




CH RTP 23.690

SERVICE ROAD CROSS SECTIONS

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN	APP	REV	DESCRIPTION	DATE	DRN	APP
P2	SERVICE ROAD B3 KERB CHANGED TO B2	03.06.21	P.H.	R.C.					
P1	SERVICE ROAD CROSS SECTIONS UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					

--	--	--	--	--	--	--	--	--	--




Designed	P.HUNJAN
Date	17.01.2020
Drawn	P.HUNJAN
Approved	J.SPARK
Date	17.01.2020
PS Number	PS837926A




Project Details	MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT
Drawing Title	ROAD CROSS SECTIONS HATHAWAY / SERVICE ROAD SHEET 2 OF 3

Sheet	06 of 12
Scale	1:100 H 1:50 V @ A1
Project Ref	1801844
Stage No	02
Drawing No	201
Rev	A


LEGEND	
	EXISTING SURFACE
	DESIGN SURFACE




CH 112.090



CH 99.861




CH 87.361




CH 74.862


SERVICE ROAD CROSS SECTIONS



CH 20.895



CH 13.916




CH 10.000

DRIVEWAY CROSS SECTIONS

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

P2	SERVICE ROAD B3 KERB CHANGED TO B3	03.06.21	P.H.	R.C.																
P1	SERVICE ROAD AND DRIVEWAY CROSS SECTIONS UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL				03.06.21	P.H.	R.C.								
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.																
REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.											






Designed Date: P.HUNJAN 17.10.2020
Drawn: P.HUNJAN
Approved Date: J.SPARK 17.10.2020
PS Number: PS837926A



Project Details: MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT
Drawing Title: ROAD CROSS SECTIONS SERVICE ROAD / DRIVEWAY SHEET 3 OF 3

Sheet 07 of 12	
Scale: 1:100 H 1:50 V @ A1	
Project Ref: 1801844	Stage No: 02
Drawing No: 202	Rev: A



Alignment C



Point no	Easting	Northing	RL
C1	745902.741	5838732.733	435.195
C2	745900.748	5838743.430	435.250
C3	745903.623	5838756.320	435.323
C4	745916.627	5838754.012	435.323
C5	745914.890	5838740.920	435.250
C6	745909.338	5838731.562	435.195

Curve no	L	Radius	Arc	A	B	X	Y	I	Mid point RL
C1 - 2	41.236	15.450	11.119	0.990	0.740	2.765	2.676	2.780	435.222
C2 - C3	87.491	9.550	14.583	2.651	1.963	3.568	3.046	3.646	435.287
C3 - C4	87.491	9.550	14.583	2.651	1.963	3.568	3.046	3.646	435.360
C4 - C5	87.491	9.550	14.583	2.651	1.963	3.568	3.046	3.646	435.287
C5 - C6	41.236	15.450	11.119	0.990	0.740	2.765	2.676	2.780	435.222

Alignment A

Point no	Easting	Northing	RL
A1	745877.817	5838640.693	433.656
A2	745887.621	5838647.536	433.919




Curve no	L	Radius	Arc	A	B	X	Y	I	Mid point RL
A1 - A2	90.050	8.450	13.281	2.478	1.834	3.235	2.742	3.320	433.787



Alignment B


Point no	Easting	Northing	RL
B1	745894.214	5838646.346	433.919
B2	745901.049	5838636.551	434.128

Curve no	L	Radius	Arc	A	B	X	Y	I	Mid point RL
B1 - B2	89.945	8.450	13.265	2.472	1.830	3.232	2.740	3.316	433.979



LEGEND

- STORMWATER DRAIN, PIT & PROPERTY INLET
- MELBOURNE WATER DRAIN & PIT
- SWALE DRAIN
- SEWER & MAINTENANCE STRUCTURES
- HOUSE DRAIN
- TACTILE PAVERS (INDICATIVE ONLY)
- EXISTING HOUSE DRAIN
- RETAINING WALL
- PAVEMENT TREATMENT
- CONCRETE EDGE STRIP WITH SUBSOIL DRAIN, "NO ROAD" SIGN & BARRIER
- LIMIT OF WORKS
- EXISTING TREE TO BE REMOVED
- PERMANENT SURVEY MARK
- TEMPORARY BENCH MARK
- PROPOSED DRIVEWAY



1:200 H 1:20 V @ A1

ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
P3	SERVICE ROAD B3 KERB CHANGED TO B2	03.06.21	P.H.	R.C.					
P2	KERB PROFILES REFLECTED	19.05.21	P.H.	M.J.					
P1	KERB A & B UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					

Maple Lane Estate

Designed: P.HUNJAN
Date: 17.01.2020

Drawn: P.HUNJAN

Approved: J.SPARK
Date: 17.01.2020

PS Number: PS837926A

BW Beveridge Williams

Suite 3/180 Eleanor Dr
Lucas VIC 3350
ph: 03 5327 2000
www.beveridgewilliams.com.au

Project Details: MAPLE LANE ESTATE
STAGE 02
CITY OF BALLARAT








Drawing Title: COURTBOWL LAYOUT
& INTERSECTION DETAILS (SHEET 1 OF 2)
HATHAWAY CLOSE AND SERVICE ROAD

Sheet 08 of 12

Scale: 1:200 @ A1

Project Ref: 1801844
Stage No: 02
Drawing No: 300
Rev: A

\\bllm601p1\data\1801844 - 255 Dyson Drive, Alfreton\Eng\Stage 2\Drawings\1801844-02-300-INT.dwg



Alignment I

Point no	Easting	Northing	RL
I1	745857.788	5838639.113	433.335
I2	745843.286	5838641.689	433.280
I3	745843.638	5838643.658	433.214
I4	745843.989	5838645.627	433.280
I5	745867.743	5838641.411	433.465

Curve no	I	Radius	Arc	A	B	X	Y	I	Mid point RL
1-2	111.859	1.945	3.798	0.856	0.628	0.912	0.699	0.949	433.254

Alignment G

Point no	Easting	Northing	RL
G1	745858.311	5838628.542	432.975
G2	745853.955	5838621.606	433.133

Curve no	I	Radius	Arc	A	B	X	Y	I	Mid point RL
G1-G2	22.491	21.000	8.243	0.403	0.302	2.058	2.038	2.061	433.014

Alignment H


Point no	Easting	Northing	RL
H1	745844.753	5838624.806	433.016
H2	745853.076	5838629.642	432.958

Curve no	I	Radius	Arc	A	B	X	Y	I	Mid point RL
H1-H2	31.884	17.522	9.751	0.674	0.505	2.430	2.383	2.438	432.987

Alignment D


Point no	Easting	Northing	RL
D1	745857.788	5838639.113	433.343
D2	745858.505	5838635.971	433.181

Curve no	I	Radius	Arc	A	B	X	Y	I	Mid point RL
1-2	111.859	1.945	3.798	0.856	0.628	0.912	0.699	0.949	433.254




LEGEND

- STORMWATER DRAIN, PIT & PROPERTY INLET
- MELBOURNE WATER DRAIN & PIT
- SWALE DRAIN
- SEWER & MAINTENANCE STRUCTURES
- HOUSE DRAIN
- TACTILE PAVERS (INDICATIVE ONLY)
- EXISTING HOUSE DRAIN
- RETAINING WALL
- PAVEMENT TREATMENT
- CONCRETE EDGE STRIP WITH SUBSOIL DRAIN, "NO ROAD" SIGN & BARRIER
- LIMIT OF WORKS
- EXISTING TREE TO BE REMOVED
- PERMANENT SURVEY MARK
- TEMPORARY BENCH MARK
- PROPOSED DRIVEWAY



ISSUED FOR CONSTRUCTION

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
P3	DRIVEWAY SETOUT UPDATED	03.06.21	P.H.	R.C.					
P2	KERB PROFILES AND DRIVEWAY SETOUT REFLECTED	19.05.21	P.H.	M.J.					
P1	KERB A & B UPDATED	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					




Designed: P.HUNJAN
Date: 17.01.2020
Drawn: P.HUNJAN
Approved: J.SPARK
Date: 17.01.2020
PS Number: PS837926A




Project Details: MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT
Drawing Title: INTERSECTION DETAILS (SHEET 2 OF 2)
Project Ref: 1801844 Stage No: 02 Drawing No: 301 Rev: A

Sheet 09 of 12
Scale: 1:200 @ A1
Project Ref: 1801844 Stage No: 02 Drawing No: 301 Rev: A



\\bawill\p1\Drawings\1801844 - 255 Dyson Drive, Alfreton\Eng\Stage 2\Drawings\1801844-02-300-INT.dwg




- NOTES**
1. LINEMARKING TO BE EXTENDED AT LEAST 6m FROM THE TANGENT POINT
 2. LINEMARKING IN ACCORDANCE WITH AS1742.
 3. TGS1 TO BE INSTALLED IN ACCORDANCE WITH VICROADS RDN 06-06 - JULY 2010
 4. ALL STREET NAME SIGNS AT INTERSECTIONS TO INCLUDE RELEVANT STREET NUMBERING.
 5. ALL LINE MARKING PAINT SHALL BE LONG LIFE TYPE. LATERAL WORKS AND ARROWS BEING COLD APPLIED PLASTIC TROWELLED INTO PLACE (MATERIAL DEGADUR PLASTELINE) AND LONGITUDINAL LINES BEING EXTRUDED THERMOPLASTIC MATERIAL.

ISSUED FOR CONSTRUCTION

© COPYRIGHT All rights reserved
Beveridge Williams & Co. Pty Ltd has granted a licence to the principle to use this document for its intended purpose.
No unauthorised copying is permitted

REV	DESCRIPTION	DATE	DRN	APP	REV	DESCRIPTION	DATE	DRN	APP
P2	SIGNAGES ADDED	19.05.21	P.H.	M.J.					
P1	REMOVED BALLARAT-CARNGHAM ROAD LINEMARKING	26.11.20	P.H.	J.S.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					




Designed Date: P.HUNJAN 17.10.2020
 Drawn: P.HUNJAN
 Approved Date: J.SPARK 17.10.2020
 PS Number: PS837926A




Project Details: MAPLE LANE ESTATE
 STAGE 02
 CITY OF BALLARAT
 Drawing Title: SINGAGE AND LINEMARKING

Sheet 10 of 12
 Scale: 1:200 @ A1
 Project Ref: 1801844
 Stage No: 02
 Drawing No: 350
 Rev: A



LEGEND	
	EXISTING SURFACE
	DESIGN SURFACE
	DRAINAGE PIPE/PIT
	EXISTING DRAINAGE PIPE/PIT
	HYDRAULIC GRADE LINE
	DENOTES 20mm CLASS 3 FOR BACKFILL.
	DENOTES RED DREDGE OR OTHER APPROVED QUARRIED PRODUCT.

ISSUED FOR CONSTRUCTION



PIT NUMBER	PIT TYPE	INTERNAL DIMENSION		INLET		OUTLET		COVER LEVEL (m)	DEPTH (m)	STANDARD DRAWING	REMARKS
		WIDTH (mm)	LENGTH (mm)	DIAMETER (mm)	INVERT LEVEL(m)	DIAMETER (mm)	INVERT LEVEL(m)				
		P07.5	JUNCTION PIT	2100	1200	1350	430.89				
1	SIDE ENTRY PIT	900	900	450	431.879	525	431.829	433.573	1.744	BCC SD - P1 - 1	PROVIDE STEP IRONS
2	SIDE ENTRY PIT	900	900	450	432.081	450	432.031	433.788	1.757	BCC SD - P1 - 1	PROVIDE STEP IRONS
3	SIDE ENTRY PIT	900	900	450	432.233	450	432.183	434.045	1.862	BCC SD - P1 - 1	PROVIDE STEP IRONS
4	JUNCTION PIT	900	900	375	433.174	450	432.474	434.491	2.017	BCC SD - P10 - 1	PROVIDE STEP IRONS
5	SIDE ENTRY PIT	900	900	375	433.347	375	433.297	434.778	1.48	BCC SD - P1 - 1	PROVIDE STEP IRONS
6	SIDE ENTRY PIT	900	900	375	433.408	375	433.408	434.777	1.369	BCC SD - P1 - 1	PROVIDE STEP IRONS
7	SIDE ENTRY PIT	900	900	300	433.077	300	432.577	434.045	1.468	BCC SD - P1 - 1	PROVIDE STEP IRONS
15	SIDE ENTRY PIT	750	900	300	433.24	300	433.19	434.276	1.086	BCC SD - P1 - 1	
16	JUNCTION PIT	600	900	300	433.442	300	433.442	434.572	1.13	BCC SD - P10 - 1	
8	JUNCTION PIT	600	900	375	432.772	375	432.722	433.621	0.9	BCC SD - P10 - 1	
9	JUNCTION PIT	900	900	300	433.342	375	433.292	434.689	1.397	BCC SD - P10 - 1	PROVIDE STEP IRONS
10	JUNCTION PIT	600	900	225	434.428	300	434.378	435.352	0.975	BCC SD - P10 - 1	
17	JUNCTION PIT	600	900	225	434.553	225	434.503	435.299	0.797	BCC SD - P10 - 1	
18	JUNCTION PIT	600	900	225	435.151	225	435.151	435.774	0.624	BCC SD - P10 - 1	
11	SIDE ENTRY PIT	900	900	300	431.81	300	431.76	433.071	1.312	BCC SD - P1 - 1	PROVIDE STEP IRONS.
12	SIDE ENTRY PIT	900	900	300	431.865	300	431.865	433.062	1.198	BCC SD - P1 - 1	
13	JUNCTION PIT	600	900	300	432.096	300	432.046	433.226	1.18	BCC SD - P10 - 1	PROVIDE HEAVY DUTY I/D
14	GRATED ENTRY PIT	600	900	300	432.125	300	432.125	433.13	1.006	BCC SD - P9	PROVIDE HEAVY DUTY I/D

REV	DESCRIPTION	DATE	DRN.	APP.	REV	DESCRIPTION	DATE	DRN.	APP.
P4	DRAINAGE LONG SECTION UPDATED FOR DRIVEWAY	03.06.21	P.H.	R.C.					
P3	DRAINAGE LONG SECTION AND PIT SCHEDULE UPDATED	19.05.21	P.H.	M.J.					
P2	DRAINAGE LONG SECTION BACKFILL UPDATED	15.12.20	P.H.	R.C.					
P1	DRAINAGE UPDATED	16.11.20	P.H.	M.J.	A	FOR APPROVAL	03.06.21	P.H.	R.C.
P0	ISSUED FOR INFORMATION	05.11.20	P.H.	J.S.					

HORIZONTAL

VERTICAL

Designed Date	P.HUNJAN 17.10.2020
Drawn	P.HUNJAN
Approved Date	J.SPARK 17.10.2020
PS Number	PS837926A

Suite 3/180 Eleanor Dr
Lucas VIC 3350
ph: 03 5327 2000
www.beveridgewilliams.com.au

Project Details		MAPLE LANE ESTATE STAGE 02 CITY OF BALLARAT		Sheet 12 of 12	
Drawing Title		DRAINAGE LONGITUDINAL SECTIONS & PIT SCHEDULE (SHEET 2 OF 2)		Scale 1:500 H 1:50 V @ A1	
Project Ref	Stage No	Drawing No	Rev		
1801844	02	401	A		